

Gulf Stream™

SWIMMING POOL
HEAT PUMPS

Made in the **USA**

Top Notch
QUALITY
Best
WARRANTY



HI-5 Series
5 Years Labor/10 Years Parts Warranty

AHRI CERTIFIED™
www.ahridirectory.org

Gulf Stream™

SWIMMING POOL
HEAT PUMPS

5 Years Labor/10 Years Parts- Limited Warranty

*See complete warranty for details



Features:

Benefits:

Performance and Efficiency

-  Super Sized Evaporator Coil (Patent Pending)
-  100% Full Flow Titanium Turbo Heat Exchanger
-  Ultra-Quiet 825rpm Fan Motor
-  Thermal Expansion Valve
-  Chill Buster (optional)

This is where efficiency begins (4 sided design)
Higher Performance in colder weather
Largest in the Industry

Lifetime warranty against corrosion
100% Titanium
Turbo design for maximum heat transfer into your pool
All 2" plumbing to maintain efficient full water flow

Ultra-Quiet and efficient operation only 56db

Refrigerant regulated for maximum efficiency in all types of weather

Reverse Gas defrost allows heating in conditions below freezing
Units can also cool the pool

Intelligent Control and Design

-  Sensible Automation
-  Solar Ready Differential Control
-  Advanced Diagnostic LCD Display
-  Even Heat
-  Triple Thermostat
-  Durable ABS Cabinet

Capable of automating your pool/spa combo
Controls valves and thermostat operation
Compatible with all external automation

Automate your solar pool heating for the perfect hybrid system
Maximizes efficiency and control

Notifies you of potential service issues in real words –not codes
Back lit display, multiple languages, and digital lockout standard

Override the timer to maintain your desired temperature anytime

Individual controls for pool, spa and solar thermostats

Rattle free. Rust proof. UV protected for lifetime durability

State of the Art Manufacturing

-  Helium (He) Testing
-  Mass Flow Charging
-  Interlocked testing Stations
-  Final Run Test

Factory leak detection 100 times more accurate than our competitors
ensuring optimized performance

Computerized refrigerant filling with no human error
Accurate to 1/100th of an ounce ensuring each unit is "Perfect"

Computerized quality control testing process can't be bypassed

Tests every component, in every unit, every time
A "Perfect" unit every time for the ultimate piece of mind

Units Specs	Hi 110	Hi 125	Hi 150
BTU/COP* <small>Outside of AHRI 1160 Test Standard</small>	110,000/6.4	120,000/6.3	136,000/6.0
AHRI High Test Point	99,000/6.0	109,000/5.9	124,000/5.4
AHRI Low Test Point	66,000/4.1	74,000/4.1	85,000/4.0
Min Amps/Max Breaker	37/40	37/50	37/50
Weight (Shipping)	218 LBS (253 LBS)	218 LBS (253 LBS)	222 LBS (257 LBS)
Dimensions (Shipping)	31x31x38 (33x31x43)	31x31x38 (33x31x43)	31x31x38 (33x31x43)



WWW.GULFSTREAMHEATPUMP.COM

MADE IN U.S.A.

